

September 23, 2021

ADDENDUM 03

BID SPECIFICATION REVISION RE BARTOW COUNTY GA FLAP GRANT RESURFACING PROJECT

The quantities on the bid schedule for Chitwood Road have been corrected. Please use the attached Proposed Schedule of Items when submitting your bid proposal.

Received and included in the bid package

---

Name and Title

Date



PROPOSED SCHEDULE OF ITEMS  
 CHITWOOD COVE ROAD RESURFACING PROJECT  
 Project #: 00151410

Item #	Item	Unit	Unit Cost	Charge
	<b>Alternate One – Surface Treatment Leveling</b>			
402-1812	85 LBS/SY RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	385 TN		
424-5007	SINGLE SURFACE TRTMT, STN SIZE 7 , GP 1 OR 2	8,213 SY		
413-0750	TACK COAT	500 GL		
	<b>Alternate Two – Open Graded Interlayer</b>			
415-5000	ASPHALTIC CONCRETE OPEN GRADED CRACK RELIEF INTERLAYER, GP 2 ONLY, INCL BITUM MATL & H LIME	450 TN		
413-0750	TACK COAT	310 GL		
	<b>Base Bid</b>			
150-1000	TRAFFIC CONTROL	LS		
402-1802	RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H LIME	125 TN		
402-3103	135 LBS/SY RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME	600 TN		
653-1501	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, WHITE	7,500 LF		
653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	7,500 LF		
653-1704	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	20 LF		

**CHITWOOD COVE ROAD TOTAL** \$ \_\_\_\_\_

**TOTAL BID** \$ \_\_\_\_\_